



Hampshire County Health Department
HC 71, Box 9
Augusta, WV 26704
(304) 496-9640 Fax: (304) 496-9650

April 6, 2005

Hampshire County Planning Commission
P. O. Box 883
Romney, WV 26757

Dear Sirs;

This office has reviewed a plat of survey for Michaela M. Puno to create lot Ranch View Estates located at the intersection of Route 50/21 and 50/19, and further referenced as Gore District, Tax Map 36, Parcel 5, Deed book 396, Page 47. This subdivision consists of 68.767 acres containing 24 lots. All lots require a percolation test and a sewage disposal area of 10,000 square feet where no development or structures other than the septic system shall be permitted. These lots are to be developed with individual wells and septic systems to serve a single family dwellings.

Percolation test results are within limits as set forth by West Virginia CSR 16-1. Six foot soil observation holes indicate no restrictions due to water table or shallow bedrock within the designated sewage disposal area **except as noted on the Health Department subdivision application.**

The plat of survey dated March 15, 2005 is hereby approved by the Hampshire County Health Department. Any changes or revisions to the Health Department stamped and signed plat, or subsequent final plats approved based upon the approved plat, will make this approval null and void.

This approval is not a permit for individual water systems or individual sewer systems. Applications for permits must be made separately to the Hampshire County Health Department.

Sincerely,

A handwritten signature in black ink, appearing to read "Jim Kinder R.S.", written in a cursive style.

Jim Kinder R.S.

cc: Michaela M. Puno

REPORT SHEET

FOR

PERCOLATION AND SIX FOOT HOLE TESTING

Subdivision Name Ranch View Estates County Hampshire
 Total Number of Lots 24 Name of Applicant M. PONO
 Name of Certified Installer Responsible for Testing Bob Blumens
 Installer Certification No. 54-00-0204 Installer Signature [Signature]

Lot No.	Percolation Test Results (Minutes Per Inch of Fall)				Average Result	Six Foot Hole Results		Date Conducted
	Depth to Water	Depth to Rock				Depth to Water	Depth to Rock	
24" 1	80	45	59	30	53.5	Get	Get	10/25/04
18" 2	55	70	73	68	54			
18" 3	81	46	60	61	62			
II 4	23	30	27	32	28.5			
II 5	50	55	50	60	54			
II 6	40	35	51	43	42			
II 7	57	52	58	40	52			
24" 8	31	37	29	28	31			
24" 9	41	46	32	51	41			
24" 10	23	37	30	33	31			
18" 11	18	16	21	27	19			
24" 12	39	41	48	35	41			
24" 13	48	36	47	38	42			
18" 14	22	28	27	31	27			
II 15	70	82	81	55	72			
II 16	62	72	46	49	57			
C.O. 18" 17	40	32	27	30	32			
C.O. 48" 18	33	27	31	40	32			
C.O. II 19	17	21	21	25	21			
C.O. 18" 20	20	21	36	17	22			
24 21	41	38	31	35	36			
24 22	31	37	28	42	35			
24 23	25	31	20	18	24			
24 24	19	23	18	26	21			

(Attach additional pages if needed)

C.O. = Curtain Drain II is CLASS II system